

**Cemetery Retaining Wall Removal, Richland Center, WI**  
**Section 00 41 43**  
**Bid Form**  
**4/19/2017**

Bid Item Ref. No.	Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
<b>Cemetery Retaining Wall Removal</b>					
1	Remove Existing Asphalt Pavement	SY	1,240		
2	Sawcut Asphalt	LF	80		
3	Salvage and stockpile retaining wall blocks (Half of Existing Wall - 1,230+/- VSF)	LS	1		
4	Remove and Dispose Existing Retaining Wall (Half of Existing Wall - 1,230+/- VSF)	LS	1		
5	Common Excavation (Salvage Existing Topsoil, Remove Existing Base Aggregate and haul to Richland Center Landfill, Grade & Construct Slope, Fill existing roadbed with excess material, haul any additional excess material to Richland Center Landfill, Respread Existing Salvaged Topsoil)	LS	1		
6	Import Topsoil from Stockpile at Richland Center Landfill and Respread Topsoil on Existing Roadbed (4" Thick)	CY	140		
7	Erosion Mat DOT Class I, Type A Biodegradable w/ Seed & Fertilizer	SY	2,400		
8	Remove and Dispose Existing Tree	EA	8		
9	Silt fence	LF	500		
<b>Total - Cemetery Retaining Wall Removal</b>					

The TOTAL BID PRICE is:

\_\_\_\_\_ Dollars (\$ \_\_\_\_\_)

Unit Prices have been computed in accordance with paragraph 11.03.B of the General Conditions.